

TEMPORARY PARTITION NOTES:

1. COORDINATE ALL TEMPORARY PARTITION TYPES AND LOCATIONS AND GATE LOCATIONS WITH CONTRACTING OFFICER
2. LOCATE VERTICAL FRAMING TO PREVENT INTERFERENCE WITH LIGHT FIXTURES
3. SECURE PLYWOOD TO PARTITION FRAMING WITH SCREWS AT 12" O.C. VERT.
4. REPAIR / REPLACE ANY DAMAGED FLOOR SLAB OR WALL FINISHES DUE TO INSTALLATION OR REMOVAL OF TEMPORARY PARTITIONS
5. ALL BARRIERS MUST BE PAINTED WHITE WHERE EXPOSED TO CUSTOMER AREAS.

DATE	DEFENSE COMMISSARY AGENCY DIRECTORATE OF ENGINEERING FORT LEE, VIRGINIA - LACKLAND AFB, TEXAS		DESIGN STANDARD
JUN 2022	TITLE TEMPORARY PARTITIONS FOR PHASED WORK	REF.	013216.10-05
		REV.	