### **DESIGN CRITERIA**

#### GENERAL

- A. While Guide Specifications are continually being updated to incorporate the specified manufacturer's product improvements, it is the A/E's responsibility to verify with the basis-of-design manufacturer that each product specification is current. Provide written notification to the DeCA Project Manager when this verification has been completed.
- B. Rotating files are used to display damaged (i.e., salvaged) merchandise that is for sale to customers. Typically the unit is located within a cased gypsum wallboard opening between the Damaged Merchandise Room (RM. 23) and the Damaged Merchandise Sales Niche (RM. 24). While one side of cabinet is accessible to customers for product display, the opposite side is open to the salvage room for re-stocking.
- C. A typical damaged merchandise display case assembly consists of a single starter unit with one add-on unit. The starter unit is 45" wide. The add-on unit is 38" wide. If a larger damaged merchandise display space is available, each add-on unit will increase overall width of assembly by 38". Only one starter unit is required per assembly. Locate foot pedal operator on salvage room side of unit. Provide cased opening, allowing +/- 2" clearance on both sides and top of assembled unit for construction / installation tolerances. Provide closures at same matching sales area décor.

#### 2. DESIGN CHARRETTE PHASE RESPONSIBILITIES

- A. During the design charrette process, the A/E (working with DeCA personnel) will develop a definitive floor plan of the commissary indicating operational equipment (drawn to scale with required end panels and clearances, etc.); and will develop an Equipment List for same indicating quantity, size, and description. Upon completion of this list, DeCA will review the list and incorporate additional operational equipment necessary for a complete and functional commissary. They will also identify responsibility for equipment as follows:
  - 1. Government-Furnished/Government-Installed (GF/GI).
  - 2. Government-Furnished/Contractor-Installed (GF/CI).
  - 3. Contractor-Furnished/Contractor-Installed (CF/CI).

## 3. CONTRACT DOCUMENT PHASE RESPONSIBILITIES.

- A. The Contract Documents shall include the equipment list developed during the design charrette process, clearly identifying responsibility for all equipment. To facilitate and expedite technical review by DeCA, the Contract Documents shall use DeCA equipment item numbers to key both the contractor-furnished and government-furnished equipment to the Drawings.
- B. If applicable, DeCA will provide the A/E with a list of existing government-owned equipment to be re-used in the new or renovated facility. The A/E shall evaluate the identified equipment to determine suitability, and confirm utility requirements for removal and relocation into the new or renovated facility. If applicable, list or note on the Contract Specifications/Drawings any equipment to be salvaged or relocated by the construction contractor.
- C. On addition / alteration projects, provide specific guidance on the Contract Documents regarding disposition of salvaged equipment (i.e., will it become the property of the contractor or turned over to DRMO). Turn-in of salvaged equipment is the responsibility of the Commissary Store Director or designated Government representative. When the contractor is required to remove and/or otherwise dispose of commissary equipment such as display and storage shelving, display cases, refrigeration equipment and walk-in-boxes, the contractor will be required to sign DD Form 1348-1 "Receipt Release Documents" prepared by the Commissary Store Director or designated Government representative. The A/E shall clearly identify any equipment that will become the

June 2022 10 56 23 1

# DeCA COMMISSARY DESIGN GUIDANCE 10 56 23 ROTATING MODULAR SYSTEM

- property of the contractor for salvage, and clearly identify that all other operational equipment shall remain the property of DeCA.  $\frac{1}{2} \int_{\mathbb{R}^{n}} \frac{1}{2} \int_{\mathbb{R}^{n}}$
- D. Verify that adequate space is available (both floor space and ceiling clearance) for all specified equipment.

**END OF SECTION** 

June 2022 10 56 23 2