



NOTES:

1. 23 09 16 TO FURNISH AND INSTALL ALL WORK NECESSARY TO ESTABLISH COMMUNICATIOAN WITH RMCS AND CONTROL OF EQUIPMENT AS SPECIFIED.
2. RMCS TO FOLLOW SEQUENCE OF OPERATION FOR OPERATING AND STAGING EXHAUST FANS AND MOTORIZED LOUVERS (IF ANY) AND MONITORING CURRENT TRANSDUCERS FOR PROOF OF RUN AND DETERMINING FAN FAILURE.

## RMCS CONTROL FOR RECEIVING AREA EXHAUST FANS

NO SCALE

DATE  JUN 2022	DEFENSE COMMISSARY AGENCY DIRECTORATE OF ENGINEERING FORT LEE, VIRGINIA - LACKLAND AFB, TEXAS		DESIGN STANDARD  230916-21
	TITLE  RMCS EXHAUST FAN CONNECTION	REF.	
		REV.	